

# COTTON COLLEGE STATE UNIVERSITY

PANBAZAR, GUWAHATI – 781001, ASSAM, INDIA

[www.ccsu.ac.in](http://www.ccsu.ac.in) :: +91-361-2733530 :: registrar@ccsu.ac.in

Ref. No.: CCSU/EC/2015/001/.....

Date:

## Notice Inviting Tender

Sealed tenders from contractors are invited for the work mentioned below,

SI. NO.	NIT No.	Works
1	NIT NO 1 of 2017-18 Dated: 11.04.2017	Removal of ceiling, placing of gypboard ceiling at CS& IT building 3 <sup>rd</sup> floor Computer Lab

The details are provided herewith. Last date of submission of sealed tenders to the undersigned is 26<sup>th</sup> April, 2017 up-to 2:00 P.M. and the tenders will be opened on same date at 3:00 PM. sealed tenders are to be submitted during office hours. Participated contractors may attend at the time of opening of the tenders as per date and time mentioned above.

  
Registrar

Memo No.: CCSU/EC /2015/001/...297-301

Date: 21/4/17

Copy for information to:

1. PS to Vice Chancellor, CCSU
2. Finance Officer, CCSU
3. Executive Engineer
4. System Manager, CCSU to upload this notice in the University website.
5. Office File

(1)

# COTTON COLLEGE STATE UNIVERSITY

PANBAZAR, GUWAHATI – 781001, ASSAM, INDIA

[www.ccsu.ac.in](http://www.ccsu.ac.in) :: +91-361-2733530 :: registrar@ccsu.ac.in

No. CCSU/EC/2015/001/

Date: -

Detail Tender Notice No 1 of 2017-18

Cotton College State University invites tender from contractor for “**Removal of ceiling, placing of gypboard ceiling at CS& IT building 3<sup>rd</sup> floor Computer Lab**”. The Tender should be submitted latest by 14:00hrs on 26<sup>th</sup> April 2017 and will be opened on the same date at 15:00 hrs.

## 1. Terms and Condition:-

The contractors should fulfil the condition below:-

- 1.1. Contractor should be registered with APWD/University/Any other Govt. agency. Copy of the up-to date registration should be submitted along with the tender.
- 1.2. Rates should be quoted in figures and words in the price bid.
- 1.3. PAN/GRN no and supporting document of the same has to be furnished along with the tender.
- 1.4. Successful tenderer should have to sign an agreement in 100 Rupees stamp paper.
- 1.5. Successful tenderer should have to deposit 10% of quoted value as security deposit which will be released after one month from the date of issue of completion certificate.
- 1.6. CCSU reserves the rights to accept, consider or reject any or all applications without assigning any reasons thereof. The decision of CCSU in respect of selection of party will be intimated by office order and shall be final. All disputes in this connection shall be settled in Kamrup metro jurisdiction only.

## Bill of Quantity:

Sl. No.	APWD SOR 2013-14	Item Description	Quantity	Unit
		<b>DISMANTLING WORKS</b>		
1	23.2	Dismantling all types of ceiling, partition and wall lining and stacking the materials as directed by the department for all levels		
		12 x 6	72	Sqm
		<b>GYPBOARD CEILING</b>		
2	7.2.1	Supplying, fitting, fixing and painting where necessary (one coat primer and two coats of paint) M/F Suspended Ceiling which includes G.I. perimeter channels of size 0.55mm thick (having one flange of 20mm and another flange of 30mm and a web of 27mm) along with perimeter of ceiling, screw fixed to brick wall/ partition with the help of nylon sleeves and screws, at 610mm c/c. Then suspending G.I. intermediate channels of size 45mm (0.9mm thick with two equal flanges of 15mm each) from the soffit at 1220mm c/c with ceiling angle of width 25mmx10mmx0.55mm thick fixed to soffit with		



2

# COTTON COLLEGE STATE UNIVERSITY

PANBAZAR, GUWAHATI – 781001, ASSAM, INDIA

[www.ccsu.ac.in](http://www.ccsu.ac.in) :: +91-361-2733530 :: registrar@ccsu.ac.in

		<p>G.I.cleat and steel expansion fasteners. which includes filling and finishing the tapered and square edges of the boards with jointing compound, joint paper tape and two coats of drywall topcoat suitable for Gypboard complete at all levels as specified and directed. (For light fittings, providing opening for doors, window, ventilators etc, cut out made with frame of perimeter channel supported suitably to be measured and paid separately where necessary).</p> <p>Ceiling section of 0.55mm thickness having knurled web of 51.5mm and two equal flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clip and in direction perpendicular to the intermediate channel at 457mm c/c, 9.5mm/12.5mm tapered edge Gypboard (conforming to IS:2095-1982) is then screw fixed to ceiling section with 25mm long drywall screws at 230mm c/c. Screw fixing is done mechanically either with screw driver or drilling machine with suitable attachment. Finally, the boards are to be jointed and finished so as to have a flush look</p>		
		(ii) 12 mm thick		
		12 x 6	72	Sqm
		<b>WIRE NETTING WORKS</b>		
3	24.11	Providing bird proof hexagonal galvanised wire netting at ceiling level of Assam type building including fitting and fixing with first class local wood frame of size 50mm x 25mm and beads of size 25mm x 10mm (for fitting and fixing the net with wooden frame) including lifting and fitting the same in position etc. complete as directed including two coats kiricide oiling of timber works.		
		(12+12+6+6)x.30	10.8	Sqm

20/9/12.

3

# COTTON COLLEGE STATE UNIVERSITY

PANBAZAR, GUWAHATI – 781001, ASSAM, INDIA

[www.ccsu.ac.in](http://www.ccsu.ac.in) :: +91-361-2733530 :: [registrar@ccsu.ac.in](mailto:registrar@ccsu.ac.in)

## PRICE BID

SI No.	Name of Work	Estimated amount in Rs.	Quoted amount Rs. (Figure and word)
1	Removal of ceiling, placing of gypboard ceiling at CS& IT building 3 <sup>rd</sup> floor Computer Lab	Rs. 83,213.00 (Eighty Three Thousand Two Hundred and Thirteen only)	

Signature of Tenderer

  
20/9/17

(4)